


NOTES:

- 1 - CONCRETE GRADE 25/13
- 2 - CONCRETE COVER = 20mm
- 3 - REINFORCEMENT TO BE PLACED WITH MAIN STRANDS RUNNING IN LONGEST DIRECTION
- 4 - SLABS TO BE CAST IN STEEL MOULDS WITH SIDES CHAMFERED 5mm. TOP OF SLAB TO HAVE "VASTRAP" PATTERN

QUANTITIES:

MASS - 30kg
CONCRETE - 12,5 l

REV	AUTH	DATE	REVISIONS		BY	CHK'D	REFERENCE DRAWINGS	
			INDEX REFERENCE					
			 NamPower	SUBSTATION TRENCH PRE-CAST SLAB TRENCH COVER				
CHK'D	MB	14.9.21						
DRAWN	IA	06.9.21	DAVIDZO NAMATE		12.44/16573			REV
SCALE	1 : 10 ON A4		15.9.21					0